BRUHAT BENGALURU MAHANAGARA PALIKE
EXECUTIVE ENGINEER (ELECRICALS) DASARAHALLI ZONE

SCHEDULE-B

Indent Number: BBMP/2021-22/EL/WORK_INDENT50079

Of work :Annual Maintanance of street lights package D-2 in Shettyhalli Surrounding Area ward no 12 .

Issued to :M/s.CHIKKANNA G.(CHETHAN ELECTRICALS)

SNo	Item Name	Unit	Estimate Quantity	Rates Quoted By Contractor	
				Rate	In Figures
1	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. 36/40 W fluorescent tube light street lighting system.	Each	20	685.45	Rupees Six Hundred Eighty Five And Paise Forty Five Only
2	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below. 125W HPMV Park lighting system.	Each	68	756.29	Rupees Seven Hundred Fifty Six And Paise Twenty Nine Only
3	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed belowPoles with 250W HPSV street lighting system.	Each	1884	1019.41	Rupees One Thousand Nineteen And Paise Forty One Only

For CHETHAN ELECTRICALS

PROPRIETOR

Executive Engineer (Ele)
Bruhath Bangalore Mahanagara Pa...
Dasarahalli Zone

Scanned with OKEN Scanner

4	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for various type of street lighting systems as detailed below 400 watts HPSV street light /High mast lighting system.	Each	132	1118.08	Rupees One Thous... Hundred Eighteen An... Eight Only
5	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 24 Watt to 40 Watt LED Park/ street lighting system.	Each	5	880.01	Rupees Eight Hundred Eighty And Paise One Only
6	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 40 Watt to 65 W LED street Light lighting system.	Each	182	1147.43	Rupees One Thousand One Hundred Forty Seven And Paise Forty Three Only
7	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 90W LED street light lighting system.	Each	55	1377.66	Rupees One Thousand Three Hundred Seventy Seven And Paise Sixty Six Only

For CHETHAN ELECTRICALS

PROPRIETOR

Executive Engineer (Ele)
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone

Scanned with OKEN Scanner

	tion and Maintenance of LED street ng system including replacement of ged/failed/fused out components like LED vers, MCPCB, surge protective device,, witches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for110/120 watt LED street light lighting system	Each	1	1575.5	Rupees One Thousand Five Hundred Seventy Five And Paise Fifty Only
9	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers, MCPCB, surge protective device,, Switches , wires, Holders, Starter observing weather proofing technic confirming to IP 65 standards. and , switching ON/OFF of street lights at specified timing and Pole numbering , Preparing ward wise ,street wise street light data bank , furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 150/180 watt LED street light /High mast lighting system.	Each	1	1871.51	Rupees One Thousand Eight Hundred Seventy One And Paise Fifty One Only
10	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.300mmx450mmx214mm	Each	5	5127	Rupees Five Thousand One Hundred Twenty Seven Only
11	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947 100 to 125Amps	Each	15	7200	Rupees Seven Thousand Two Hundred Only
12	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.50-63 Amps SP	Each	16	723	Rupees Seven Hundred Twenty Three Only
13	Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers.	Each	18	4030	Rupees Four Thousand Thirty Only

For CHETHAN ELECTRICALS

PROPRIETOR

Executive Engineer (Ele)
Bruhath Bangaloro Mahanagara P...
Dasarahalli Zone

Scanned with OKEN Scanner

14	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments.6 sqmm	Mtr	10	70	Rupees Seventy Only
15	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.6 sqmm	Each	100	7	Rupees Seven Only

For CHETHAN ELECTRICALS

PROPRIETOR

Executive Engineer (Ele)
Dasarahalli Zone.
Bruhat Bengaluru Mahanagara Palike.

Scanned with OKEN Scanner